

## Test Report

FOR: **dB Sound Control**  
Mt. Airy, NC

**Floor Covering Impact Reduction**  
**RAL-IFC18-004**

CONDUCTED: 2018-03-21

Page 1 of 8

ON: Laminate wood flooring over dB 4 Pro underlayment

### TEST METHOD

Riverbank Acoustical Laboratories has been accredited by the U.S. Department of Commerce, National Institute of Standards and Technology (NIST) under the National Voluntary Laboratory Accreditation Program (NVLAP) for this test procedure (NVLAP Lab Code: 100227-0). The test reported in this document conformed explicitly with ASTM E2179-03 (2009): "Standard Test Method for Laboratory Measurement of the Effectiveness of Floor Coverings in Reducing Impact Sound Transmission Through Concrete Floors". The single number rating was calculated according to ASTM E989-06 (2012): "Standard Classification for Determination of Impact Insulation Class (IIC)." The measurements were recorded using a real time analyzer and a rotating microphone boom incorporating a spatial average. The rotation speed of the boom was set at 32 seconds per revolution and the linear integration time of the analyzer was set at 32 seconds. The impact sound pressure levels (ISPL) were measured for each of the twenty-one standard one-third octave bands from 50 Hz through 5000 Hz for both the standard concrete slab and the provided specimen. The laboratory's standard concrete floor is a fully cured 152.40 mm (6.0 in.) thick concrete floor installed directly in the laboratory's 4.27 m (14.0 ft.) by 2.44 m (8 ft.) test opening. A complete description of the measuring procedure and room qualifications is available upon request.

### DESCRIPTION OF THE SPECIMEN

The test specimen was designated by the manufacturer as Laminate wood flooring over dB 4 Pro underlayment. The building contractor and RAL staff compiled a detailed construction specification as follows:

#### Underlayment

---

Trade Name:	dB 4 Pro
Material:	Felt over vinyl sheet
Installed:	Loose laid over concrete slab, felted side down
Overall Dimensions:	2438.4 mm (96 in.) x 2743.2 mm (108 in.)
Measured Thickness:	6.63 mm (0.261 in.)
Overall Weight:	48.99 kg (108 lbs)
Mass per Unit Area:	4.71 kg/m <sup>2</sup> (0.96 lb/ft <sup>2</sup> )
Joints:	Sealed with tape

## Test Report

**dB Sound Control**  
2018-03-21

**RAL-IFC18-004**  
Page 2 of 8

### Floor Covering

Material: Wood-look laminate over fiberboard flooring tiles  
Installed: Loose laid over underlayment  
Tile Dimensions: 1290 mm (50.787 in.) x 194 mm (7.638 in.)  
Tile Thickness: 6.6 mm (0.26 in.)  
Overall Weight: 62.14 kg (137 lbs)  
Mass per Unit Area: 5.97 kg/m<sup>2</sup> (1.22 lb/ft<sup>2</sup>)  
Joints: Locking edge design

### Concrete Slab

Material: Wire-reinforced concrete  
Dimensions: 4 @ 609.6 mm (24 in.) x 4267.2 mm (168 in.)  
Thickness: 152.4 mm (6.0 in.)  
Overall Weight: 3,467.71 kg (7,645 lbs)  
Mass per Unit Area: 333.27 kg/m<sup>2</sup> (68.26 lb/ft<sup>2</sup>)  
Installation: The slab was isolated from the sill by rubber pads  
Joints: Underside sealed with acoustical caulk and tape  
Top filled with general purpose sand, sealed with ready mix compound

### Physical Measures

Size: 2.44 m (96.00 in.) wide by 4.27 m (168.00 in.) long  
Thickness: 172.21 mm (6.78 in.)  
Weight: 3578.90 kg (7890.00 lbs.)  
Mass per Unit Area: 343.97 kg/m<sup>2</sup> (70.45 lbs./ft<sup>2</sup>)  
Transmission Area: 10.40 m<sup>2</sup> (112.00 ft<sup>2</sup>)

### Test Aperture

Size: 4.27 m (14.0 ft.) by 2.44 m (8 ft.)  
Filler Wall: None  
Sealed: Entire periphery (both sides) with dense mastic

### Test Environment

#### Source Room

Volume: 132.6 m<sup>3</sup> (4,681.0 ft<sup>3</sup>)  
Temperature: 23±0°C (73±0°F)  
Humidity: 50±3%

#### Receive Room

Volume: 81.7 m<sup>3</sup> (2,884.3 ft<sup>3</sup>)  
Temperature: 23±0°C (74±0°F)  
Humidity: 52±1%

**Test Report**

**dB Sound Control**  
2018-03-21

**RAL-IFC18-004**  
Page 3 of 8



Figure 1 – Specimen mounted in test opening



Figure 2 – Underlayment installed over concrete slab

**Test Report**

**dB Sound Control**  
2018-03-21

**RAL-IFC18-004**  
Page 4 of 8



Figure 3 – Underside of test specimen

## Test Report

**dB Sound Control**  
2018-03-21

**RAL-IFC18-004**  
Page 5 of 8

### TEST RESULTS

1/3 Octave Center Frequency (Hz)	Normalized Impact SPL, $L_0$ , Bare Standard Concrete Floor (dB)	Normalized Impact SPL, $L_c$ , Floor Covering Installed (dB)	Reduction in Impact SPL, $L_d$ , ( $L_0 - L_c$ ), (dB)	Impact SPL of Floor Covering on a Reference Concrete Slab, $L_{ref, c}$ , (dB)
100	55	53	2.0	65.0
125	61	59	2.0	65.5
160	61	57	4.0	64.0
200	64	59	5.0	63.5
250	68	62	6.0	63.0
315	72	63	9.0	60.5
400	70	53	17.0	53.0
500	72	51	21.0	49.5
630	71	41	30.0	41.0
800	71	38	33.0	38.5
1000	70	32	38.0	34.0
1250	71	28	43.0	29.0
1600	74	25	49.0	23.0
2000	71	20	51.0	21.0
2500	70	14	56.0	16.0
3150	72	8	64.0	8.0

Increase in Impact Insulation Class  $\Delta IIC = 25$

Impact Insulation Class,  $IIC_c$  for  $L_{ref, c}$

$IIC_c = 53$

**Test Report**

**dB Sound Control**  
2018-03-21

**RAL-IFC18-004**  
Page 6 of 8

TEST RESULTS (Continued)

The measured impact sound pressure levels (ISPL) are tabulated in each of the twenty-one standard one third octave bands from 100 Hz through 3150 Hz for both the standard concrete slab and the three sample materials. The reduction in ISPL calculated for the floor covering has been applied to a reference concrete floor with an IIC = 28 as described in the standard. The increase in impact insulation class,  $\Delta IIC$  as well as the  $IIC_c$  for the floor covering on a reference concrete slab has also been calculated. An \* indicates that the value has been adjusted for background noise levels and reflects a lower limit. A graphic presentation of the data appears on the following page.

Tested by   
Marc Sciaky  
Experimentalist

Report by   
Malcolm Kelly  
Acoustician


Approved by   
Eric P. Wolfram  
Laboratory Manager

Test Report

dB Sound Control  
2018-03-21

RAL-IFC18-004  
Page 7 of 8

**Floor Covering Impact Reduction**  
Laminate wood flooring over dB 4 Pro underlayment



**ΔIIC=25**

**IMPACT REDUCTION OF FLOOR COVERING  
ON A CONCRETE FLOOR**

**Test Report**

**dB Sound Control**  
2018-03-21

**RAL-IFC18-004**  
Page 8 of 8

**APPENDIX A: Instruments of Traceability**

Specimen: Laminate wood flooring over dB 4 Pro underlayment (See Full Report)

<u>Description</u>	<u>Model</u>	<u>Serial Number</u>	<u>Date of Certification</u>	<u>Calibration Due</u>
Bruel & Kjaer Pulse Analyzer - System4	Type 3560-C	2639093	2017-08-02	2018-08-02
Bruel & Kjaer Mic And Preamp D	Type 4943-B-001	2311440	2017-09-22	2018-09-22
Bruel & Kjaer Tapping Machine-WoodCase	3204	226940	2017-07-11	2018-07-11
Bruel & Kjaer Pistonphone	Type 4228	2781248	2017-08-02	2018-08-02
EXTECH_62	SD700	A.083662	2017-11-20	2018-11-20
EXTECH_63	SD700	A.083663	2017-11-20	2018-11-20

---

END